



Architectural Testing

## TEST REPORT

Rendered to:

**LMT-Mercer Group, Inc.**

For:

**PRODUCT: 4" x 4" and 5" x 5" PVC Porch Posts  
with Aluminum Reinforcing**

**Report No.: D3198.01-119-19**

**Report Date: 01/28/14**

**Test Record Retention Date: 12/20/17**



**Architectural Testing**

**TEST REPORT**

D3198.01-119-19

January 28, 2014

---

**TABLE OF CONTENTS**

1.0	General Information.....	1
2.0	Axial Load Compression Tests.....	2
3.0	Uplift Load Tests .....	10
4.0	Tensile Testing.....	11
5.0	Closing Statement .....	14
	Revision Log.....	15
	Appendix A - Drawings	
	Appendix B - Photographs	

## **TEST REPORT**

Rendered to:

LMT-MERCER GROUP, INC.  
322 Lake Avenue  
P.O. Box 1147  
Hartville, Ohio 44632

Report No.: D3198.01-119-19  
Test Dates: 12/03/13  
Through: 12/20/13  
Report Date: 01/28/14  
Test Record Retention Date: 12/20/17

### **1.0 General Information**

#### **1.1 Product**

4" x 4" and 5" x 5" PVC Porch Post with Aluminum Reinforcing

#### **1.2 Project Description**

Architectural Testing was contracted by LMT-Mercer Group, Inc. to evaluate the structural performance of their 4" x 4" and 5" x 5" PVC porch posts with aluminum reinforcing. The evaluation was for concentric axial loads in compression, uplift loads as well as tensile testing of material specimens taken from the aluminum tube insert.

#### **1.3 Product Description**

All test samples were provided by the manufacturer for testing. The 4" x 4" hollow PVC column samples measured 108" long and had a 2-7/16" outside diameter aluminum tube through the center. The 5" x 5" hollow PVC column samples measured 108" long and had a 3-1/4" outside diameter aluminum tube through the center. Each sample was comprised of a molded PVC sleeve which surrounded an aluminum tube insert, four PVC filler strips, and two PVC mounting brackets.

## 1.4 Qualifications

Architectural Testing in York, Pennsylvania has demonstrated compliance with ANS/ISO/IEC Standard 17025 and is consequently accredited as a Testing Laboratory (TL-144) by International Accreditation Service, Inc.

## 1.5 Reference Standards

ASTM B 221-05, *Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles and Tubes*

ASTM E 8 / E 8M-08, *Standard Test Methods for Tension Testing of Metallic Materials*

## 2.0 Axial Load Compression Tests

### 2.1 Test Equipment

The test fixture consisted of a flat steel support attached to a rigid steel column at the top. The bottom consisted of a hydraulic jack positioned on a leveling fixture, fitted with a flat steel bearing plate and a 50,000 pound capacity load cell. Test duration, load, and deflection were recorded electronically throughout the test.

### 2.2 Test Setup

The columns were installed into the compression fixture with no physical connections between the column and fixture. The compression fixture was plumbed using a "PLS-5" laser plumbing device, and while applying a minimal preload to hold the test sample in place, the column was leveled with a 78" level. An electronic linear displacement transducer was positioned at the mid-point of each of two axes on each column to measure lateral displacements about the X- and Y-Axes of the column.

### 2.3 Test Procedure

Each test sample was inspected prior to testing to verify size and general condition of the materials, assembly, and installation. No potentially compromising defects were observed prior to the tests. Each test began with a small initial load and was loaded at a steady, uniform load rate until the test sample failed. Lateral displacements, test load, and time were electronically recorded throughout the test. The ultimate load and mode of failure were recorded for each test.

## 2.4 Test Results

Test loads were concentric axial compression. X- and Y-Axis displacements were measured at the column's mid-height.

**Specimen No. 1**  
**4" x 4" PVC Porch Post with Aluminum Reinforcing**  
**Test Date: 12/03/13**

Test Load (lb)	Displacement (inches)	
	X-Axis	Y-Axis
0	0.00	0.00
1286	0.15	-0.02
2112	0.20	0.00
3382	0.26	0.02
4042	0.28	0.02
5155	0.31	0.04
6127	0.37	0.06
7086	0.42	0.07
8100	0.50	0.08
9274	0.67	0.13
<b>10080</b>	<i>Ultimate Load</i>	

**Specimen No. 2**  
**4" x 4" PVC Porch Post with Aluminum Reinforcing**  
**Test Date: 12/03/13**

Test Load (lb)	Displacement (inches)	
	X-Axis	Y-Axis
0	0.00	0.00
1094	0.18	-0.03
2326	0.25	-0.02
3310	0.29	-0.01
4530	0.33	0.01
5176	0.35	0.03
6215	0.40	0.07
7322	0.45	0.10
8203	0.53	0.13
9261	0.73	0.21
<b>9761</b>	<i>Ultimate Load</i>	

2.4 Test Results (Continued)

**Specimen No. 3**  
**4" x 4" PVC Porch Post with Aluminum Reinforcing**  
**Test Date: 12/03/13**

Test Load (lb)	Displacement (inches)	
	X-Axis	Y-Axis
0	0.00	0.00
1160	0.17	-0.01
2146	0.21	-0.01
3208	0.24	0.00
4400	0.27	0.01
5179	0.29	0.02
6235	0.32	0.04
7417	0.37	0.06
8376	0.45	0.10
9254	0.57	0.14
<b>10269</b>	<i>Ultimate Load</i>	

**Specimen No. 4**  
**4" x 4" PVC Porch Post with Aluminum Reinforcing**  
**Test Date: 12/03/13**

Test Load (lb)	Displacement (inches)	
	X-Axis	Y-Axis
0	0.00	0.00
1389	0.12	0.07
2561	0.19	0.09
3262	0.21	0.11
4395	0.25	0.14
5152	0.27	0.17
6186	0.31	0.20
7163	0.36	0.24
8200	0.45	0.30
9275	0.60	0.41
<b>9911</b>	<i>Ultimate Load</i>	

2.4 Test Results (Continued)

**Specimen No. 5**  
**5" x 5" PVC Porch Post with Aluminum Reinforcing**  
**Test Date: 12/03/13**

Test Load (lb)	Displacement (inches)	
	X-Axis	Y-Axis
0	0.00	0.00
1403	0.18	0.03
2369	0.24	0.04
3163	0.27	0.05
4260	0.31	0.06
5071	0.33	0.07
6105	0.36	0.07
7286	0.39	0.07
8270	0.41	0.07
9182	0.43	0.07
10253	0.46	0.08
11341	0.50	0.08
12121	0.55	0.09
13486	0.66	0.11
14328	0.87	0.14
<b>14439</b>	<i>Ultimate Load</i>	

2.4 Test Results (Continued)

**Specimen No. 6**  
**5" x 5" PVC Porch Post with Aluminum Reinforcing**  
**Test Date: 12/03/13**

Test Load (lb)	Displacement (inches)	
	X-Axis	Y-Axis
0	0.00	0.00
1133	0.11	0.01
2191	0.16	0.02
3267	0.19	0.02
4246	0.21	0.02
5146	0.22	0.03
6509	0.24	0.04
7174	0.25	0.05
8372	0.27	0.06
9370	0.30	0.07
10122	0.32	0.08
11222	0.36	0.09
12247	0.41	0.12
13204	0.49	0.15
14407	0.66	0.23
<b>14853</b>	<i>Ultimate Load</i>	

2.4 Test Results (Continued)

**Specimen No. 7**  
**5" x 5" PVC Porch Post with Aluminum Reinforcing**  
**Test Date: 12/03/13**

Test Load (lb)	Displacement (inches)	
	X-Axis	Y-Axis
0	0.00	0.00
1477	0.18	0.06
2148	0.23	0.07
3095	0.27	0.07
4088	0.29	0.08
5033	0.31	0.08
6302	0.34	0.09
7222	0.35	0.09
8319	0.38	0.10
9080	0.41	0.10
10161	0.45	0.11
11136	0.49	0.13
12315	0.57	0.15
13337	0.70	0.18
14123	0.91	0.24
<b>14398</b>	<i>Ultimate Load</i>	

2.4 Test Results (Continued)

**Specimen No. 8**  
**5" x 5" PVC Porch Post with Aluminum Reinforcing**  
**Test Date: 12/03/13**

Test Load (lb)	Displacement (inches)	
	X-Axis	Y-Axis
0	0.00	0.00
1368	0.12	0.02
2301	0.17	0.02
3170	0.20	0.02
4267	0.22	0.02
5052	0.24	0.02
6238	0.26	0.02
7422	0.29	0.03
8190	0.30	0.03
9235	0.33	0.04
10272	0.36	0.05
11172	0.39	0.07
12187	0.45	0.08
13372	0.58	0.11
14249	0.80	0.13
<b>14676</b>	<i>Ultimate Load</i>	

## 2.5 Test Summary

Results are ultimate load capacity of individual specimens and should not be used as safe working values or design load values.

### 4" x 4" PVC Porch Post with Aluminum Reinforcing

Specimen No.	Ultimate Load (lb)	Deviation From Average	Failure Mode
1	10080	+0.7%	Lateral Buckling at Midspan
2	9761	-2.4%	
3	10269	+2.6%	
4	9911	-0.9%	
Average:	10005		
Standard Deviation:	219		
Coefficient of Variation:	2.2%		

### 5" x 5" PVC Porch Posts with Aluminum Reinforcing

Specimen No.	Ultimate Load (lb)	Deviation From Average	Failure Mode
1	14439	-1.0%	Lateral Buckling at Midspan
2	14853	+1.8%	
3	14398	-1.3%	
4	14676	+0.6%	
Average:	14592		
Standard Deviation:	213		
Coefficient of Variation:	1.5%		

### 3.0 Uplift Load Tests

#### 3.1 Test Equipment

The specimens were tested to ultimate capacity in tension utilizing a SATEC Unidrive, Model MII 50 UD Universal Test Machine (ICN: Y002011).

#### 3.2 Test Setup

The testing machine was fitted with pressure treated Southern Yellow Pine (SYP) 2x8 wood boards at the top and bottom to accommodate anchorage of the column brackets. The mounting brackets were secured to the 2x8 with four #10-12 x 1-1/2" (0.132" minor diameter) philips drive, trim head, zinc plated, carbon steel screws. Each mounting bracket attached to the aluminum insert with four #10-16 x 1" (0.136" minor diameter) philips drive, pan head, zinc plated, self-starting, carbon steel screws and the PVC sleeve was attached to each mounting bracket with two #10-16 x 1" (0.136" minor diameter) philips drive, pan head, zinc plated, self-starting, carbon steel screws. Tests were conducted at lab ambient temperature (68°F ± 4°F). Reference photographs in Appendix B for test setup.

#### 3.3 Test Procedure

After securing each column into the test machine, the load was applied at a uniform rate of 0.05 in/min. until failure. The test duration, ultimate test load, and mode of failure were recorded for each test.

#### 3.4 Test Results

Results are ultimate load capacity of individual specimens and should not be used as safe working values or design load values.

**4" x 4" PVC Porch Post with Aluminum Reinforcing**  
**Test Date: 12/19/13**

Specimen No.	Ultimate Load (lb)	Percent Deviation From Average	Failure Mode
1	1544	+0.8%	Bracket Failure
2	1501	-2.0%	
3	1552	+1.3%	
<b>Average:</b>	<b>1532</b>		
<b>Standard Deviation:</b>	<b>27</b>		
<b>Coefficient of Variation:</b>	<b>1.8%</b>		

### 3.4 Test Results (Continued)

**5" x 5" PVC Porch Post with Aluminum Reinforcing**  
**Test Date: 12/19/13 and 12/20/13**

Specimen No.	Ultimate Load (lb)	Percent Deviation From Average	Failure Mode
<b>1</b>	1405	+5.8%	Bracket Failure
<b>2</b>	1386	+4.4%	
<b>3</b>	1193	-10.2%	
<b>Average:</b>	<b>1328</b>		
<b>Standard Deviation:</b>	<b>117</b>		
<b>Coefficient of Variation:</b>	<b>8.8%</b>		

Reference photographs in Appendix B for mode of failure.

### 4.0 Tensile Testing

Re: ICC-ES™ AC273 - Section 4.1

#### 4.1 General

Tensile tests were performed on dog-bone specimens machined from the aluminum tube inserts used in the column assemblies for the purpose of verifying the material specification.

#### 4.2 Test Specimens

Tensile test specimens were machined from aluminum tube used in the axial compression tests. Specimen size was per FIG 13 of ASTM E 8 / E 8M - 08 for large-diameter tubular products.

#### 4.3 Test Procedure

The specimens were tested using an Instron® Model 3369 Universal Test Machine with Instron® "T" grips and operating at a uniform cross-head speed of 0.2 in/min. Strain was measured using an Instron® Model 2630-100 Series Clip-on Extensometer with a 2 inch gage length.

#### 4.4 Test Results

##### 4" x 4" PVC Porch Post Aluminum Tube Insert

Test Date: 12/19/13

Sample ID	Width (in)	Thickness (in)	Modulus of Elasticity (ksi)	Yield Strength (ksi)	Tensile Strength (ksi)	Elongation (%)
S1-A	0.501	0.079	10206	36.0	41.0	9.8
S1-B	0.500	0.082	10018	36.4	40.8	12.2
S1-C	0.500	0.083	9977	35.2	40.5	13.9
S2-A	0.500	0.081	10373	35.0	39.6	12.4
S2-B	0.500	0.081	10427	35.5	39.8	11.9
S2-C	0.500	0.082	10727	35.3	39.9	13.5
<b>Minimum:</b>			9977	35.0	39.6	9.8
<b>Maximum:</b>			10727	36.4	41.0	13.9
<b>Mean:</b>			10288	35.6	40.2	12.3
<b>Standard Deviation:</b>			281	0.5	0.6	1.4
<b>Coefficient of Variation:</b>			2.7%	1.5%	1.4%	11.8%

##### 5" x 5" PVC Porch Post Aluminum Tube Insert

Test Date: 12/19/13

Sample ID	Width (in)	Thickness (in)	Modulus of Elasticity (ksi)	Yield Strength (ksi)	Tensile Strength (ksi)	Elongation (%)
L1-A	0.502	0.072	11807	35.5	39.5	12.7
L1-B	0.500	0.074	9857	35.0	39.2	16.5
L1-C	0.501	0.070	11719	36.0	39.8	11.5
L2-A	0.501	0.071	9810	37.3	41.1	13.8
L2-B	0.500	0.069	10973	36.1	40.5	13.9
L2-C	0.502	0.069	10806	37.0	41.0	14.5
<b>Minimum:</b>			9810	35.0	39.2	11.5
<b>Maximum:</b>			11807	37.3	41.1	16.5
<b>Mean:</b>			10829	36.2	40.2	13.8
<b>Standard Deviation:</b>			866	0.9	0.8	1.7
<b>Coefficient of Variation:</b>			8.0%	2.4%	2.0%	12.2%

#### 4.5 Analysis of Test Results

Per LMT Mercer Group, Inc., the material used to reinforce their 4" x 4" and 5" x 5" PVC porch post tested and reported herein was specified as extruded 6005-T5 aluminum. The following criteria are listed under ASTM B 221, Table 2 - *Mechanical Property Limits*, for 6005-T5:

- Tensile strength, min, psi - 38,000
- Yield strength, min, psi - 35,000
- Elongation in 2 in., min, % - N/A (applies only to tests performed prior to shipment)

	<b>Min. Tensile Strength (psi)</b>	<b>Min. Yield Strength (psi)</b>
6005-T5	38,000	35,000
4" x 4" PVC Porch Post Aluminum Tube Insert	40252	35580
5" x 5" PVC Porch Post Aluminum Tube Insert	40191	36155

## 5.0 Closing Statement

Architectural Testing will service this report for the entire test record retention period. Test records that are retained such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation will be retained by Architectural Testing, Inc. for the entire test record retention period.

Results obtained are tested values and were secured using the designated test methods. This report does not constitute certification of this product nor an opinion or endorsement by this laboratory. It is the exclusive property of the client so named herein and relates only to the specimens tested. This report may not be reproduced, except in full, without the written approval of Architectural Testing, Inc.

For ARCHITECTURAL TESTING, INC.:

---

Adam J. Schrum  
Technician I  
Structural Systems Testing

---

V. Thomas Mickley, Jr., P.E.  
Senior Project Engineer  
Structural Systems Testing

AJS:vtm/jas

Attachments (pages): This report is complete only when all attachments listed are included.

Appendix A - Drawings (7)

Appendix B - Photographs (2)

### Revision Log

<u>Rev. #</u>	<u>Date</u>	<u>Page(s)</u>	<u>Revision(s)</u>
0	01/28/14	N/A	Original report issue

**APPENDIX A**

**Drawings**



4

THIS DRAWING IS THE PROPERTY OF THE LMT-MERCER GROUP, INC. AND EMODIES A CONFIDENTIAL PROPRIETARY DESIGN IN WHICH THE LMT-MERCER GROUP, INC. RETAINS ALL PATENT AND OTHER RIGHTS, INCLUDING EXCLUSIVE RIGHTS TO MAKE, USE, SELL, OR OTHERWISE DISPOSE OF THE DESIGN OR ANY INFORMATION REGARDING IT TO ANY UNAUTHORIZED PERSON.

3




Test sample complies with these details.  
Deviations are noted.

Report # D3198.01-19-19  
Date 1/17/17 Tech AJS

2


REV	DESCRIPTION

1



B

4



B

A

VOLUME: 30.69 CUBIC INCHES

A

**LMT-MERCER GROUP**  
 LMT-MERCER GROUP, INC.  
 690 PURITAN AVENUE  
 LAWRENCEVILLE, NJ 08648

TOLERANCES UNLESS SPECIFIED  
 FRACTIONAL ± 1/64  
 ANGULAR ± 1/2°  
 .XX ± .010  
 .XXX ± .002  
 .XXXX ± .0005

SHEET DESCRIPTION:

THIRD ANGLE PROJECTION

DESIGN: JGF  
 APPROVED: \_\_\_\_\_  
 RELEASE DATE: MM/DD/YY

CUSTOMER: LMT  
 PART NUMBER: 25697  
 MOLD NUMBER: 1049  
 MATERIAL: HDPE  
 SHRINKAGE: N/A

4 X 4 Forch Post Filler Strip.dwg

SHEET 1 OF 1

4

3

2

1

4

THIS DRAWING IS THE PROPERTY OF THE LMT-MERCER GROUP, INC., AND EMBODIES A CONFIDENTIAL PROPRIETARY DESIGN. IT IS TO BE USED ONLY FOR THE PURPOSE AND INTENT FOR WHICH IT WAS CREATED. THE LMT-MERCER GROUP, INC. RETAINS ALL PATENT AND OTHER RIGHTS, INCLUDING EXCLUSIVE RIGHT OF USE, MANUFACTURE, SALE, REPRODUCTION, AND DISTRIBUTION. NO PART OF THIS DRAWING IS TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF THE LMT-MERCER GROUP, INC.

3



### Architectural Testing

Test sample complies with these details.  
Deviations are noted.


Report # D3198-01-119-19

Date 1/17/14 Tech ATS

2


REV	DATE	DESCRIPTION	APPROVE
1	10/13/13	INCREASED DIMENSION FROM 0.20 TO 0.25	JF

1



B

4



A

3

2

1

TOLERANCES UNLESS SPECIFIED  
 FRACTIONAL ± 1/64  
 ANGULAR ± 1/2°  
 .XX ± .010  
 .XXX ± .002  
 .XXXX ± .0005

**LMT-MERCER GROUP**  
 LMT-MERCER GROUP INC.  
 690 PURITAN AVENUE  
 LAWRENCEVILLE, NJ 08648

A

REV B

SHEET DESCRIPTION:  
 THIRD ANGLE PROJECTION

DESIGN: JGF  
 APPROVED: [Signature]  
 RELEASE DATE: MM/DD/YY

CUSTOMER: LMT  
 PART NUMBER: 25698  
 MM/DD/YY MOLD NUMBER: 1049  
 SCALE: NONE  
 MATERIAL: PP  
 SHRINKAGE: N/A  
 SHEET 1 OF 1

4


3

2

1



THIS DRAWING IS THE PROPERTY OF LMT-MERCER GROUP. IT IS TO BE USED FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED HEREIN. IT IS NOT TO BE REPRODUCED, COPIED, OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF LMT-MERCER GROUP.




# Architectural Testing

Test sample complies with these details.  
Deviations are noted.

Report # 03198.01-119-19

Date 1/17/14 Tech AJS




TOLERANCES UNLESS SPECIFIED	FRACTIONS	DECIMALS	ANGLES	SPACES
FRACTIONS	1/16	0.0005	1/16	1/16
DECIMALS	0.0005	0.0005	1/16	1/16
ANGLES	1/16	0.0005	1/16	1/16
SPACES	1/16	0.0005	1/16	1/16
APPROVED:	DESIGNED BY	CHECKED BY	DATE	SCALE
				SCALE 2:1
				MATERIAL IN A
				SHEET OF 1

4

THIS DRAWING IS THE PROPERTY OF THE LMT-MERCER GROUP, INC. AND EMBODIES A CONFIDENTIAL PROPRIETARY DESIGN IN WHICH THE LMT-MERCER GROUP, INC. RETAINS ALL PATENT AND OTHER RIGHTS, INCLUDING EXCLUSIVE RIGHTS OF INVENTION. THE RECIPIENT OF THIS DRAWING AGREES TO HOLD THE DRAWING IN CONFIDENCE AND TO NOT DISCLOSE ANY INFORMATION REGARDING IT TO ANY UNAUTHORIZED PERSON.


3



B

2

REV	DATE	APPROVED



B




Architectural Testing

Test sample complies with these details.  
Deviations are noted.

Report # D3198.01-119-19

Date 1/17/14 Tech AJS

A



A

TOLERANCES UNLESS SPECIFIED  
 FRACTIONAL ± 1/64  
 ANGULAR ± 1/2°  
 .XX ± .010  
 .XXX ± .002  
 .XXXX ± .0005

**LMT-MERCER GROUP**  
 LMT-MERCER GROUP, INC.  
 690 PURITAN AVENUE  
 LAWRENCEVILLE, NJ 08648

DESIGN: J. FATTORI 1/15/2014  
 APPROVED: B. LYNN 1/15/2014

SHEET DESCRIPTION:  
 4 PORCH POST ALUM. TUBE  
 CUSTOMER: LMT  
 PART NUMBER: 25667

THIRD ANGLE PROJECTION

SCALE: NONE MAT: SEE NOTE SHRINKAGE: N/A SHEET 1 OF 1

4

3


2

1

4

THIS DRAWING IS THE PROPERTY OF THE LMT-MERCER GROUP, INC. AND EMBODIES A CONFIDENTIAL, PROPRIETARY DESIGN IN WHICH THE LMT-MERCER GROUP, INC. RETAINS ALL PATENT AND OTHER RIGHTS, INCLUDING EXCLUSIVE RIGHTS TO MAKE, USE, SELL, OR OTHERWISE DISPOSE OF THE DESIGN OR INVENTION FOR ANY PURPOSE, AND THE RECIPIENT AGREES TO ACCEPT AND MAINTAIN THE DESIGN OR INVENTION AS A CONFIDENTIAL RELATIONSHIP FOR A SPECIFIC PERIOD OF TIME. THE RECIPIENT AGREES TO ACCEPT AND MAINTAIN THE DESIGN OR INVENTION AS A CONFIDENTIAL RELATIONSHIP FOR A SPECIFIC PERIOD OF TIME. THE RECIPIENT AGREES TO ACCEPT AND MAINTAIN THE DESIGN OR INVENTION AS A CONFIDENTIAL RELATIONSHIP FOR A SPECIFIC PERIOD OF TIME. THE RECIPIENT AGREES TO ACCEPT AND MAINTAIN THE DESIGN OR INVENTION AS A CONFIDENTIAL RELATIONSHIP FOR A SPECIFIC PERIOD OF TIME.

3



2

DATE	REV	DESCRIPTION	DATE	APPROVE
	B1	B CHANGED WALL THICKNESS	12/2013	JF

B





Architectural Testing

Test sample complies with these details.  
Deviations are noted.

Report # 03198.01-119-19

Date 1/17/14 Tech ATS

A



$\pm$  0.010  
0.075  $\pm$  0.010

B

MATERIAL : 6005 T5 ALUMINUM

A

**LMT-MERCER GROUP**  
 LMT-MERCER GROUP, INC.  
 690 PURITAN AVENUE  
 LAWRENCEVILLE, NJ 08648

TOLERANCES UNLESS SPECIFIED  
 FRACTIONAL  $\pm$  1/64  
 ANGULAR  $\pm$  1/2°  
 .XX  $\pm$  .010  
 .XXX  $\pm$  .002  
 .XXXX  $\pm$  .0005

SHEET DESCRIPTION:  
 5 PORCH POST ALUM. TUBE  
 CUSTOMER: LMT  
 PART NUMBER: 25515

THIRD ANGLE PROJECTION

DESIGN: F. LOFIUS 2/10/09

APPROVED: J. FAIORI 3/1/09

RELEASE DATE: 3/1/09

SCALE: 1=2

MAT. SEE NOTE

SHRINKAGE: N/A

SHEET 1 OF 1

4

3

2

1

**APPENDIX B**

**Photographs**



**Photo No. 1**  
**Axial Load Compression Test Setup**



**Photo No. 2**  
**Typical Uplift Test Setup**



**Photo No. 3**  
**Typical Uplift Load Test Failure**